

OREGON CORNER RESTORATION FORM

SECTION:32 TOWNSHIP: 5N RANGE: 29E V-7

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

N1/4 Section 32

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1979 LaGier used a 5/8" iron rebar which lies 30.64' West of corner.
In 1989 Edwards set a 1"x30" iron pipe with 2 3/8" brass cap.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found a 2 3/8" brass cap 10" below the surface of a graveled road stamped as below.
W.C. an aluminum tag #951 in a power pole bears N 32° 46' E 38.51'(38.51')
W.C. an aluminum tag #951 in a power pole bears S 54° 04' 01" E 29.74'(29.80')

MONUMENT DETAIL

T5NR29E
1/4 29
32
1989
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809120.74
8529756.00

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 4° 12' 44" E 35.57'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 68° 57' 25" W 45.61'

LOCATION AND COMMENTS

From the intersection of Craig road with Walls road go East on Walls 0.5 miles to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05