


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.



Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate original location of this corner:

At a mid-point position, I set a 5/8 x 30 inch iron rod with a 2 inch aluminum cap mkd: as shown, in the center of W. Walls Road, down 2 inches below the gravel.

From which:

- (RM 1) A 2 1/2 inch long MAG nail with a 1 1/2 inch stainless steel washer mkd.: WALLOWA ASSOCIATES LS 91201, in SWly face of power pole #297000, bears N 2°54' E, 33.91 ft. dist. to the face of washer.
- (RM 2) A 2 1/2 inch long MAG nail with a 1 1/2 inch stainless steel washer mkd.: WALLOWA ASSOCIATES LS 91201, in NEly face of power pole #327900, bears S 68°37' W, 55.78 ft. dist. to the face of washer.



NAD 83 Geodetic Position
Lat. 45°52'43.64116" N
Long. 119°12'29.81803" W

Established by: Trimble RTK

I hereby certify that the corner is monumented and accessories taken as described, using dual frequency carrier-phase GNSS receivers.

Witnesses: Kristina Powell, David Quittschreiber and Shar Quittschreiber



K.P. Powell



EXPIRES 12-31-22

Office of _____ County Surveyor _____ County of _____ Umatilla
State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 20__.

(COUNTY OFFICIAL)

(DEPUTY)