

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 12/14/10

CORNER DESIGNATION: L-17, The East 1/4 corner of Section 15, Township 5 North, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by Nicholas O. Walden under Contract No. 909, dated July 6, 1874. Notes state drove charred stake and raised mound of earth with pits as per instructions for 1/4 section corner.

MONUMENT AND ACCESSORIES FOUND: Found and held a fence corner with fences North, South, and West as the best remaining evidence of the original corner.

MONUMENT MARKING DETAIL:

T5NR31E  
1/4  
S15|S14  
2010  
PLS 1106

MONUMENT SET: Set a 2 3/8" brass cap on a 1 1/4"x30" galvanized iron pipe with the cap 2" above ground just Northeast of fence corner post. Monument marked as shown in "Monument Marking Detail".

New accessories:

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears S 00° E, 38.4 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears N 87° W, 27.3 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" in fence line bears N 87° W, 66.1 feet.

A 3/4" brass washer marked "PLS 1106 " 1 foot above ground level in railroad tie fence post bears N 02 1/2° E, 58.8 feet.

Attached witness post sign to fence corner post 0.5 feet Southwest of corner monument.  
Attached bearing object sign to railroad tie fence post above the brass washer. Wired bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner is located at a fence corner post with fences North, South, and West in a CRP field approximately 1300 feet +/- Easterly of Hartle Road, A.K.A. County Road No. 883. See Umatilla County Partition Plat No. 2010-28 for map reference.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, PLS  
Dean Roy

5N31L17

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-12*

*10-183-B*