

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/02/10

CORNER DESIGNATION: N-21, The Section corner common to Section 14, 13, 23, & 24 Township 5 North, Range 33 East W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set post for corner to Sections 13, 14, 23 & 24, drove charred stake, dug pits & raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T5N R33E
S14 | S13
S23 | S24
2010
PLS 1106

MONUMENT SET: Held intersection of Duroc County Road with a old field berm extending south as best remaining evidence of original corner. Set a 2 3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, with top of brass cap 6" below gravel road surface and stamped as shown in "Monument Marking Detail".

New Accessories:

- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N57°E 28.8 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears S42°E 27.3 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears S50°W, 43.2 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N77°W, 48.1 feet.

Red plastic caps on rebar accessories are marked "OR PLS 1106 WA PLS 17372". The rebar accessories are set near road shoulder. Wired a bearing object sign to each of the rebar accessories.

LOCATION AND COMMENTS: Corner is located at a point in the centerline of Duroc Road and a farmed field berm to the south. A steel tape and magnetic compass were used to measure bearings and distances to accessories.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 822072.99
E = 8675328.24


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells
Dean Roy

5N33N21



William R. Wells



renews 6-30-12

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: Jason Roberts
No.: 12-029-C