

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: V-11, The North One-Quarter Corner of Section 33, T5N., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set 1/4 Sec. post; drove charred stake; dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was reestablished by holding railroad tie "H" brace in established East-West field line/berm. Wire railroad tie "H" brace indicates railroad tie was once a fence corner or gate post between farmed fields.

MONUMENT MARKING DETAIL:

T5N R33E
1/4 S28
S33
2004
PLS 1106

MONUMENT SET: At a point immediately West of Westerly railroad tie of "H" brace, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe, 29" in the ground and surrounded with mound of earth.

New accessories to corner monument:

A 3/4" brass washer stamped "PLS 1106", nailed 1 foot above ground level in the Easterly "H" brace railroad tie bears S 85° E, 5.8 feet.

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with top 1" above ground level in a East-West field bears N 89° E, 24.7 feet.

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with top 1" above ground level in a East West field line bears East, 54.4 feet.

A blue "Deep-1 Magnet" buried 20" below ground level bears S 52° W, 44.1 feet.

Attached bearing object sign to iron rebar accessories and to railroad tie post with brass washer accessory. Buried bearing object sign with "Deep-1 Magnet". Nailed witness sign to railroad tie "H" brace post immediately East of the corner monument.

LOCATION AND COMMENTS: Corner is located in a East-West field line.


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

V5N33V11



William R. Wells



RECEIVED BY
Umatilla County
Date 4-04
Rec'd By KK
No. 04-76-B