

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: V-17, The Northeast Corner of Section 34, T5N., R33E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set post Cor. for Secs. 26, 27, 34, 35. Drove charred stake; dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was reestablished at the intersection of field lines extending North and West. Reestablished corner position was verified by survey.

MONUMENT MARKING DETAIL:

T5N R33E
S27 | S26
S34 | S35
2004
PLS 1106

MONUMENT SET: At position determined as described, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe 44" in the ground. Top of brass cap is 14" below ground surface.

New accessories to corner monument:

A silver "Deep-1 Magnet" buried 20" below ground level bears N 33° E, 31.2 feet.
A purple "Deep-1 Magnet" buried 20" below ground level bears S 36° E, 32.5 feet.
A blue "Deep-1 Magnet" buried 20" below ground level bears S 47° W, 35.1 feet.
A orange "Deep-1 Magnet" buried 20" below ground level bears N 50° W, 34.0 feet.
Buried bearing object signs with the "Deep-1 Magnets". Set steel fence post with witness sign attached, 1.5 feet North of corner monument.

LOCATION AND COMMENTS: Corner is located at corner of farmed fields. Field lines extend North and West.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

5N33V17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY

Umatilla County Surveyor

Date 4-04

Rec'd By KK

No. 04-76-B