

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: Z-13, The Standard Southwest Corner of Section 34, T5N, R33E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set post Standard Cor. for Secs. 33 and 34, land facing the S.E., drove charred stake; dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was reestablished at intersection of field line/berm extending East-West and field line/berm extending North. A burnt off, down locust post was found at the re-established corner point. A locust post bears North 86°53'27" West., 452.46 feet. This locust post appears to mark the approximate closing corner between Sections 3 and 4, T4N., R33E., W.M., although the measured distance does not match the record distance of 6.50 chains. A field line extends South from the locust post.

MONUMENT MARKING DETAIL:

S.C.
T5N R33E
S33 | S34
2004
PLS 1106

MONUMENT SET: At corner position determined as described, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe, 42" in the ground. Top of brass cap is 12" below ground surface.

New accessories to corner monument:

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground bears N 71° E, 9.5 feet.
A purple "Deep-1 Magnet" buried 20" below ground level bears S 26° E, 27.7 feet.
A blue "Deep-1 Magnet" buried 20" below ground level bears S 55 1/2° W, 41.5 feet.
A orange "Deep-1 Magnet" buried 20" below ground level bears N 66° W, 43.2 feet.
Attached bearing object sign to iron rebar accessory and buried bearing object signs with the "Deep-1 Magnets". Set steel fence post with witness sign 1.5 feet North of corner monument.

LOCATION AND COMMENTS: Corner is located in a East-West by North farmed field intersection.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

5N33Z13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY

Umatilla County Surveyor.

Date 4-04

Rec'd By KK

No. 04-76-B