

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/01/04

CORNER DESIGNATION: Z-15, The Standard South One-Quarter Corner of Section 34, T5N, R33E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William H. Odell and William L. Lewis, U.S. Deputy Surveyors under Contract No. 110, dated February 7, 1865. Record states: Set Standard Cor. for 1/4 Sec. in ravine, course, N.E. Drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was determined by single proportionate measurement between the reestablished Southwest and Southeast Standard corners of Section 34. Corner falls in a draw, 2 feet South of a East-West farmed field line.

MONUMENT MARKING DETAIL:

S.C.
T5N R33E
1/4 S34
2004
PLS 1106

MONUMENT SET: At position determined as described, set a 2 1/2" brass cap (marked as shown in "Monument Marking Detail"), on a 1 1/4" x 30" galvanized iron pipe 44" in the ground. Top of brass cap is 14" below ground level.

New accessories to corner monument:

A silver "Deep-1 Magnet" buried 20" below ground level bears N 63° E, 28.5 feet.
A purple "Deep-1 Magnet" buried 20" below ground level bears S 43° E, 36.0 feet.
A blue "Deep-1 Magnet" buried 20" below ground level bears S 45 1/2° W, 35.2 feet.
A orange "Deep-1 Magnet" buried 20" below ground level bears N 50° W, 29.5 feet.
Buried bearing object signs with "Deep-1 Magnets". Set steel fence post with witness sign attached in East-West field line 2 feet Northeast of corner monument.

LOCATION AND COMMENTS: Corner located at a East-West field line in a farmed draw facing NE.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

5N33Z15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY

Umatilla County Survey

Date 4-04

Rec'd By KK

No. 04-76-B