

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/06/09

CORNER DESIGNATION: J-9, The Southeast Corner of Section 8, Township 5 North, Range 34 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post corner sections 8, 9, 16 & 17. Land slopes to the North, Drove charred stake, dug pits, and raised mound as per instructions. The corner location was also calculated by Steve Haddock in his Survey No. 03-113-C.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R34E  
S8 | S9  
S17|S16  
2009  
PLS 1106

MONUMENT SET: Held intersection of old field berms extending east-west and south as best remaining evidence of original corner location. There are also old fence remains extending west. Set a 2 3/8" diameter brass monument on a 1 1/4" x 30" galvanized iron pipe, with cap 20" below ground level, marked as shown in "Monument Marking Detail".

New Accessories:

A silver deep-1 magnet bears North 53 1/4° East, a distance of 12.2 feet, buried 24 inches.  
A pink deep-1 magnet bears South 52° East, a distance of 19.2 feet, buried 27 inches.  
A blue deep-1 magnet bears South 46 1/2° West, a distance of 13.7 feet, buried 24 inches.  
An orange deep-1 magnet bears North 54 3/4° West, a distance of 11.3 feet, buried 25 inches.  
All magnets have bearing object signs buried near them. Set fence post 3 feet North of corner with witness sign..

LOCATION AND COMMENTS: At intersection of old field berms extending east-west and south. Old fence remains extend west.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827108.06  
E = 8690691.89


FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Matt Brockamp  
D. Palmer

\5N34J9



*William R. Wells*



*renews 6-30-12*

**RECEIVED BY**  
Umatilla County Surveyor  
Date: 4/3/2012  
Rec'd By: Stacy Hahert  
No.: 12-029-C