

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/02/10

CORNER DESIGNATION: N-3, The South Quarter Corner of Section 18, Township 5 North, Range 34 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set 1/4 section post, on level, Drove charred stake dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R34E
1 S18
4 S19
2010
PLS 1106

MONUMENT SET: Reestablished corner point on line between the calculated Southeast and monumented Southwest corners of Section 18, with the intersection of an old field berm extending North-South through corner point. Set a 2 3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, with top of brass cap 16" below ground surface in farmed field, stamped as shown in "Monument Marking Detail".

New accessories:

- A silver "deep-1" magnet buried 18" in the ground bears N 49° E, 32.0 feet.
 - A blue "deep-1" magnet buried 18" in the ground bears S 27° E, 40.3 feet.
 - A pink "deep-1" magnet buried 18" in the ground bears S 56° W, 32.1 feet.
 - An orange "deep-1" magnet buried 18" in the ground bears N 37° W, 39.9 feet.
- Buried bearing object sign with each of the "deep-1" magnet accessories.

LOCATION AND COMMENTS: Approximately 150 feet south of newer wind turbine access road, in a farmed field with field berm to the south and north. A steel tape and magnetic compass were used to measure bearings and distances of accessories.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:


N = 821810.57
E = 8683349.33

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Dean Roy

\5N34N3



Will R. Wells



renews 6-30-12

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: Jay Nelson
No.: 12-029-C