

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/10/05

CORNER DESIGNATION: 5N35, G-13, The East Quarter Corner of Section 9.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

Record of Survey No. Q-805-A states: "found rock". BPA Milton Tap Line Transmission line maps show a "rock". Survey No. 98-82-R shows a 8" x 8" by 24" basalt stone.

**MONUMENT AND ACCESSORIES FOUND:**

Found 28" x 12" x 8" stone set firmly in the ground with the top 8" exposed. Excavated stone and found no visible marks.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S9 | S10  
2005  
PLS 1106

**MONUMENT SET:**

At position of found stone set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 26" in the ground, marked as shown in Monument Marking Detail. Buried corner stone Northwest of new monument with 8 inches exposed.

**New accessories:**

A 3/4" brass washer stamped "PLS 1106", nailed 1.0 foot above ground level on a monitoring station pole bears South 50° East, 70.9 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", flush with the ground bears South 05° East, 67.6 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", flush with the ground bears South 49° West, 69.4 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", flush with the ground bears North 44° West, 36.7 feet.

Attached bearing object signs to rebar accessories and to monitoring pole. Set steel fence post with "witness" sign 1.0 foot North of brass cap monument.

**LOCATION AND COMMENTS:** Corner is located on ridge top, 2 1/2 feet Southerly of a field line fence meandering around a farmed area.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 830223.14  
E = 8728076.57

**FIRM:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

**COMPASS DECLINATION:** 18° East

Surveyor's Seal

**Witnesses:** Jason Wells, LSIT  
Brian Cole

/5N35G13



Renews 6/30/06

05-112-c