

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/22/05

CORNER DESIGNATION: 5N35, J-21, The Northeast Corner of Section 14.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 11,12, 13 & 14. Drove charred stake; dug pits; raised mound, as per instructions. The original corner was recovered on Record of Private Surveys, Survey No. 5 and on Survey No. 36, a 18 x 11 x 5 inch stone was set at the corner point. Ofner calls for a "rock" in his 1950 Survey No. Q-805-A. Lommasson calls for a stone in his Survey No. D-11-Ax. Krumbein finds a 2" iron pipe in his Survey No. S 157-C and remonuments with a aluminum cap monument in 1981.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" aluminum cap on a 2 1/2" aluminum pipe with top 2" above ground level, marked as shown in Monument Marking Detail. A steel fence post is located Southwest of corner monument. Aluminum cap is marked as shown in Monument Marking Detail.

MONUMENT MARKING DETAIL:

T5N R35E
S11 | S12
S14 | S13
1981
PLS 933

MONUMENT SET:

The existing corner monument was maintained by adding new accessories:

A silver deep-1 magnet buried 20" below ground level, bears North 41° East, 34.8 feet.

A purple deep-1 magnet buried 20" below ground level, bears South 56° East, 39.9 feet.

A blue deep-1 magnet buried 20" below ground level, bears South 48° West, 34.9 feet.

An orange deep-1 magnet buried 20" below ground level, bears North 39° West, 44.3 feet.

Buried bearing object signs with deep-1 magnets. Attached "witness" sign to existing steel fence post near corner monument.

LOCATION AND COMMENTS: Corner is located at the west edge of a draw running Northeast, about 25 feet south of East-West field line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827814.89
E = 8738338.14


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35J21



Renews 6/30/06

05-112-c