

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/24/05

CORNER DESIGNATION: 5N35, J-23, The South Quarter Corner of Section 12.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec. Drove charred stake, etc.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1 S12  
4 S13  
2005  
PLS 1106

**MONUMENT SET:**

Corner was re-established by single proportion measurement midway between the Northwest and Northeast corners of Section 13. Set a 2 1/2" brass cap on a 1 1/4" x 30" iron pipe, 28" in the ground, marked as shown on Monument Marking Detail.

**New accessories:**

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level, bears North 60° East, 34.8 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 feet above ground level, in a highway road sign post, bears South 14 1/2° East, 60.4 feet.

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level, bears South 71° West, 67.9 feet.

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level, bears North 41° West, 47.8 feet.

Wired bearing object signs to all rebar accessories, and nailed bearing object sign to highway sign post. Set steel fence post 1 foot North of monument and attached "witness" sign.

LOCATION AND COMMENTS: Corner falls in a large drainage between a farmed field to the West and State Highway 11.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 827751.69  
E = 8740948.35


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35J23

Surveyor's Seal



*William R. Wells*



*Renews 6/30/06*

05-112-c