

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/10/05

CORNER DESIGNATION: 5N35, L-13, The East Quarter Corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S16 | S15
2005
PLS 1106

MONUMENT SET:

Corner was re-established by single proportionate measurement between the Northeast and Southeast corners of Section 16. At the re-established corner point, set a 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe, 27" in the ground, marked as shown in Monument Marking Detail. The corner monument falls 2 feet West of a fence line.

New accessories:

A 3/4" brass washer stamped "PLS 1106", 1.0 feet above ground level on a railroad tie fence post bears North 09° East, 26.2 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in a North-South fence bears South 05° East, 29.7 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", cap 1" above ground level in North-South fence bears South 05° East, 54.1 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 feet above ground level on a railroad tie fence post bears North 09° West, 53.2 feet.

Attached bearing object signs to rebar accessories and to railroad ties with brass washers.

LOCATION AND COMMENTS: Corner is located 2 feet West of a North-South fence line on an unfarmed hill sloping West.

OREGON STATE PLANE COORDINATES, North Zone, NAD 83(91), International Feet:

N = 825020.52
E = 8728525.75

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35L13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06