

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/22/05

CORNER DESIGNATION: 5N35, L-21, The East Quarter Corner of Section 14.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, etc.

Corner was not recovered on Record of Private Surveys, Survey No. 5, Survey No. 16 or Survey No. 36. The corner was re-established and monumented with a post and glass bottle on Survey No. 16. In Record of Private Surveys, Survey No. 36, the corner was not recovered and was repositioned mid-way between the Northeast and Southeast Corners of Section 14, but no monument was established. State Highway Map No. 88-11-21, (1958), shows a "fence cor." at this point. I considered using the State Highway Map tie, but there is nothing left at the corner area to verify the tie. The State tie would place the corner about 25 feet further East than the single proportion position. Record of Private Surveys, Survey No.s 5 and 36, both place the corner midway and on line between the Northeast and Southeast corners of Section 14.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S14 | S13  
2005  
PLS 1106

**MONUMENT SET:**

I re-established the corner by single proportion measurement midway and on line between the Southeast and Northeast corners of section 14. At the re-established corner position, set a 2 1/2" brass cap on a 1 1/4" x 30" iron pipe with cap 20" below ground level, marked as shown on Monument Marking Detail. Corner is located 15 feet West of a North-South field berm.

**New Accessories:**

A silver deep-1 magnet buried 20" below ground level, bears North 45 1/2° East, 45.0 feet.  
A purple deep-1 magnet buried 20" below ground level, bears South 65° East, 52.5 feet.  
A blue deep-1 magnet buried 20" below ground level, bears South 45° West, 38.1 feet.  
An orange deep-1 magnet buried 20" below ground level, bears North 52° West, 51.5 feet.  
Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Located 15 feet West of a North-South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 825072.04  
E = 8738395.22


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Brian Cole

/5N35L21



*William R. Wells*



Renews 6/30/06

05-112-C