

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/13/05

CORNER DESIGNATION: 5N35, R-7, The South Quarter Corner of Section 20.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865.  
Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No. 106, J.W. Kimbrell recovered this corner and calls it at a fence intersection, E-W & S.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1 S20  
4 S29  
2005  
PLS 1106

**MONUMENT SET:**

I accepted the extended intersection of existing field lines approaching from the East and South as the best remaining evidence of the original corner location. Mr. Bill Ferguson stated the fences had been removed some years ago. The field corner is now rounded and does not form a distinct angle point. At re-established corner position, set a 2 1/2" brass cap on 1 1/4" x 30" iron pipe with cap 18" below ground level in active farmed field, marked as shown on Monument Marking Detail.

**New accessories:**

- A silver deep-1 magnet buried 24" below ground level, bears North 34° East, 34.3 feet.
  - A purple deep-1 magnet buried 24" below ground level, bears South 50° East, 35.8 feet.
  - A blue deep-1 magnet buried 24" below ground level, bears South 33 1/2° West, 43.6 feet.
  - An orange deep-1 magnet buried 24" below ground level, bears North 40 1/2° West, 41.5 feet.
- Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field. There are no nearby features except field lines.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 817217.12  
E = 8720303.78

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/5N35R7

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6/30/06*

05-112-C