

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/21/05

CORNER DESIGNATION: 5N35, X-01, The West Quarter Corner of Section 31.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N
R34E R35E
1/4
S36|S31
2005
PLS 1106

MONUMENT SET:

Corner area falls in a wheat field with no nearby features. I re-established this corner by single proportionate measurement between the Northwest and Southwest Quarters of Section 31. At the re-established corner position, set 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, with cap 18" below ground, marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet bears North 52° East, 49.9 feet.
 - A purple deep-1 magnet bears South 15° East, 54.3 feet.
 - A blue deep-1 magnet bears South 60° West, 57.7 feet.
 - An orange deep-1 magnet bears North 16° West, 53.9 feet.
- All magnets are buried 20" below ground level. Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner falls in a actively farmed field, no nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 808890.26
E = 8712545.38


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/5N35X01



William R. Wells



Renews 6/30/06