

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/04/08

CORNER DESIGNATION: Z-21, The Southeast Corner of Section 35, Township 6 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. For Secs. 1, 2, 35 & 36. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N R36E
S35|S36
S2 | S1
T5N
2008
PLS 1106

MONUMENT SET: Held railroad ties found 686 feet North and 725 feet South of corner point for departure and positioned corner on parallel of latitude between the South one-quarter corner of Section 36 and the Southwest corner of Section 35. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 24" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 42 1/2° East, 30.0 feet.
- A purple deep-1 magnet bears South 30° East, 32.1 feet.
- A blue deep-1 magnet bears South 51 1/2° West, 31.9 feet.
- An orange deep-1 magnet bears North 34 1/2° West, 33.8 feet.
- Deep-1 magnets are buried 20" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in a wheat field. No nearby features except railroad ties 686 feet North and 725 feet South on North-South line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 839523.45
E = 8769990.57

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36Z21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-C