

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/13/03

CORNER DESIGNATION: R-3, The South One-Quarter Corner of Section 19, Township 5 North, Range 36 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Record states: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. Under Survey No. 00-45-B, a fence corner was found and held for the corner position.

MONUMENT AND ACCESSORIES FOUND:

Found tipped over fence corner post at intersection of field lines extending East, West and South. Dug around base of post to determine it's standing position and held that position for corner point. A new fence corner post was erected between the time we tied the corner point and when the monument was set. New fence post bears N 45° E, 2.5 feet from old corner post.

MONUMENT MARKING DETAIL:

T5N R36E
1 S19
4 S30
2003
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe with cap 4" above ground level marked as shown in "Monument Marking Detail". Corner is surrounded by farmed fields.

New accessories:

- A grey Deep-1 Magnet buried 16" in ground bears N 42° E, 27.1 feet.
- A purple Deep-1 Magnet buried 16" in ground bears S 40° E, 30.7 feet.
- A blue Deep-1 Magnet buried 16" in ground bears S 44° W, 30.6 feet.
- An orange Deep-1 Magnet buried 16" in ground bears N 38° W, 28.1 feet.
- Buried bearing object signs, below ground, with all Deep-1 magnets. Nailed witness sign to new fence corner post bearing N 45° E, 2.5 feet from corner..

LOCATION AND COMMENTS: Corner located at intersection of field lines East-West and South.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
V5N36R3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY
Umatilla County Surveyor
Date 5-03
Rec'd By KK
No. 03-65-B