

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 6/06/2014

CORNER DESIGNATION:

Z-17, Section Corner common to Sections 34 and 35 Township 6 North, Range 37 East and Sections 3 and 2, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set stone 14"x11"x8" basalt, corner for sections 34, 35, 2 & 3 on a steep hill side facing the east."

Surveyor Paul W.P. Tomkins noted in his October 15, 1999 survey, shown on Umatilla County Survey record of surveys 99-258-C, "Corner was originally established by Odell and Lewis under contract No. 110 dated Feb. 7, 1865, as a basalt stone, evidence found:

We found a firmly set basalt stone 15"x11"x7" in mound of smaller stones and earth, on a Northerly facing prominence on a steep Northeast facing slope.

Perpetuation Information:

Set a 5/8" x 30" iron rebar with yellow cap marked "Tomkins Surveying" at the location of the rock and placed the rock alongside. A 12" Fir bears N35°W 9.0 feet from the corner and a 10" Fir bears S5°W 4.5 from the corner, trees were not scribed, however bearing object signs were attached to them and they were painted with 6" wide red bands."

MOUNUMENT AND ACCESSORIES FOUND:

A 5/8" iron rebar with Yellow Cap "Tomkins" +/- one foot above ground and a basalt stone one to two feet downhill.

A 10" Douglas fir with bearing tag and no blaze.

A 12" Douglas fir with bearing tag and no blaze.

MOUNUMENT MARKING DETAIL:

T6N
S34|S35 R37E
S3|S2
T5N
2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the position of the found 5/8" iron rebar, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap, 28" in the ground marked as shown.

The 10 inch in diameter Douglas fir with bearing tag and no blaze as show under "Monument and Accessories found" was blazed and scribed accordingly S8°E 5.00 feet distance.

The 12 inch diameter Douglas Fir with bearing tag and no blaze as show under "Monument and Accessories found" was blazed and scribed accordingly N388°W 9.6 feet distance.

An 18 inch diameter Tamarack bears S56°W, 28.6 feet distance.

A ½ inch iron rebar with cap in stone marked at top of ridge bears N62°E, 36.47 distance.

Set found stone alongside as witness.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 840643.96

E = 8796007.26

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group

5 N. Colville, Suite 200


Walla Walla WA 99362

WITNESSES: Thomas J. Boshart

Felipe G. Hernandez



A handwritten signature in cursive script, appearing to read "Greg E. Flowers".



RENEWS 12/31/15

06/29/2015