

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 6/24/2014

CORNER DESIGNATION:

Z-3, Quarter corner common to Section 31 Township 6 North, Range 37 East and Section 6, Township 5 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis, Deputy Surveyors, Contract No. 110, dated February 7, 1865. Their notes state "Set quarter corner section with stone 16x12x4, basalt."

MOUNUMENT AND ACCESSORIES FOUND:

Found old well established fences running West and North from a 6" x 6" corner post. I have accepted this corner as the best evidence of the corner position.

MOUNUMENT MARKING DETAIL:

T6N
¼ $\frac{S31}{S6}$ R37E
2014 T5N
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the southeast corner of the 6" x 6" corner post, set a 1½" x 30" galvanized iron pipe with a 2½" brass cap stamped as the quarter corner common to Section 31 Township 6 North, Range 37 East and Section 6, Township 5 North, Range 37E, from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N61°W, 10.90 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N43°E, 14.20 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S45°E, 17.20 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S46°W, 15.30 feet.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 839863.28
E = 8777941.59

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



RENEWS 12/31/15

06/29/2015