

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Section Corner common to Sections 1, 2, 11 & 12,
Township 5 North, Range 37 East, of the Willamette Meridian
Umatilla County, Oregon.


E-21

History of original corner establishment:

GLO:
George Williams, Deputy Surveyor, Contract No. 176,
20 July, 1872.
Set post for Sec. Cor. 1, 2, 11, 12 from which:
A Spruce 30 in. dia. bears S70°E 30 lks. dist.
A Spruce 18 in. dia. bears S37°W 55 lks. dist.
A Tamarack 20 in. dia. bears N10°W 25 lks. dist.

Description of evidence found:

I searched diligently for this corner but could find no evidence of the original monument or its accessories. According to testimony of local residents, this corner position falls at the site of a large sawmill which was active in this area during the 1940's and 1950's. I consider this corner to be lost and re-established its position by double proportionate means from the restored positions for the northwest and southeast corners of Section 1, the one-quarter corner common to Sections 11 and 12, and the Section corner common to Sections 3, 4, 9 and 10.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 26, 1988
PAUL W.P. TOMKINS
2360

8/26/92

Description of monument and accessories I established to perpetuate the original location of this corner:

At the double proportionate position determined above, I set a standard 1" dia. "Hoffland" galvanized iron pipe with 2-1/2" dia. Bronze cap marked as shown, flush with the surface of the ground with a mound of stones erected around the monument on the easterly edge of a dirt road which crosses over from Government Mountain Road to Saddle Mountain Road, from which:

A 23 in. dia. Engelman Spruce bears N4°E, a distance of 51.10 feet to center, with face mkd. "S1BT". An Aluminum nail is driven into a 3/4" Brass washer mkd. "WA 25893 OR 2360" in the center of the "B" on the face, which is typical for all bearing trees marked in this re-establishment.

A 12-1/2 in. dia. Western Larch bears S82°E, a distance of 10.42 feet to center, with face mkd. "S12BT".

An 11 in. dia. Western Larch bears S39°W, a distance of 25.02 feet to center, with face mkd. "S11BT".

An 8-1/2 in. dia. Western Larch bears N60°W, a distance of 46.95 feet to center, with face mkd. "S2BT".

A 6.0 foot studded "T" steel fence post is driven 1.5 ft. into the ground, North, 1.0 feet from the monument.

I affixed Umatilla County Surveyor Yellow Metal Bearing Object signs to each bearing tree. I also affixed Yellow Metal Bearing Tree signs (penalty for disturbance, etc.) to each tree.

Bearings are magnetic using a declination of 19°E.

Office of _____ County of _____
State of _____, I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 9-92

Rec'd By KK

No. 92-106-C