


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. E-5

**History of original corner establishment:**

In 1872, under G.L.O. Contract No. 176, George Williams set post for Cor. to Sec. 5, 6, 7 & 8 from which:

- A White Pine 12 in. dia. bears S53<sup>0</sup>E 42 lks.
- A White Pine 10 in. dia. bears N50<sup>0</sup>E 27 lks.
- A White Pine 8 in. dia. bears N23<sup>0</sup>W 20 lks.
- A White Pine 16 in. dia. bears S40<sup>0</sup>E 12 lks.



**Description of corner evidence found:**

Possible remains of orig. N.E. bearing tree, now a 20" Lodge Pole Pine stump with scribing "BT" plainly visible on previously opened face, facing approx. S50<sup>0</sup>W. Found 3 other stumps in area generally agreeing with orig. notes in size, with axe marks and faces, but not agreeing with bearings and distances given. No other scribing could be found. We use orig. N.E. BT to set Cor.

**Description of monument and accessories established to perpetuate the original location of this corner:**

A Record Bearing and distance from original N.E. BT, set 1"x30" Galvanized Pipe with 3" brass cap stamped:

Set pipe 26" in ground.

**Bearing Trees:**

- A 6" Fir bears N71<sup>0</sup>W 6.9 ft., scribed T5N R38E S6 BT.
- A Fir 5" dia. bears S17<sup>0</sup>W 6.5 ft., scribed: T5N R38E S7 BT.
- A Fir 12" dia. bears S40<sup>0</sup>E 27.1 ft., scribed: T5N R38E S8 BT.
- A Spruce 12" dia. bears N14<sup>0</sup>E 24.4 ft., scribed: T5N R38E S5 BT.



Attached 54-3 and 54-4 signs to all BTs. Attached brass washers stamped LS 1294 to foot blaze of all BTs. Painted blazes and 6" bank around all BTs red.



I hereby certify the above corner monument was reestablished as herein described on October 10, 1980.

- Witnesses:
- R. Orton
  - G. Wagoner
  - L. Huntsman
  - A. Hanley

Office of.....County Surveyor..... County of.....Umatilla.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the.....day of.....December....., 1980  
 David Brunson..... by.....Betty Stalton.....  
 (COUNTY OFFICIAL) (DEPUTY)