

USDA-FOREST SERVICE

Index  
File No. E-5


CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)

Tract or  
Survey No. \_\_\_\_\_ Cor.  
No. \_\_\_\_\_

T 5N R. 38E R.D. W<sup>2</sup> County UMATILLA  
Merid. WILL N.F. UMATILLA State OREGON

CORNER DIAGRAM

Description of corner evidence found:



Possible remains of orig. N.E. bearing tree, now a 20" Lodge Pole Pine stump with scribing "BT" plainly visible on previously opened face, facing approx. S50°W. Found 3 other stumps in area generally agreeing with orig. notes in size, with axe marks and faces, but not agreeing with bearings and distances given. No other scribing could be found. We use orig. N.E. BT to set Cor. 2

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER 3

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

Signature

Title

Division

Headquarters

Date

7100-52 (3 68)

151 HOWARD L. PERRY

PLS 1294

10/80

**CORNER RECORD (PERPETUATION)**

Description of monument and accessories established to perpetuate the original location of this corner:

A Record Bearing and distance from original N.E. BT, set 1"x30" Galvanized Pipe with 3" brass cap stamped:

Set pipe 26" in ground.

Bearing Trees:

A 6" Fir bears N71<sup>0</sup>W 6.9 ft., scribed T5N R38E S6 BT.

A Fir 5" dia. bears S17<sup>0</sup>W 6.5 ft., scribed: T5N R38E S7 BT.

A Fir 12" dia. bears S40<sup>0</sup>E 27.1 ft., scribed: T5N R38E S8 BT.

A Spruce 12" dia. bears N14<sup>0</sup>E 24.4 ft., scribed: T5N R38E S5 BT.

Attached 54-3 and 54-4 signs to all BTs. Attached brass washers stamped LS 1294 to foot blaze of all BTs. Painted blazes and 6" band around all BTs red.

CROWN ZELLERBACH

T5N R38E

S6 | S5

S7 | S8

OR 1980  
PLS 1294

1°

18

—

11

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

E-5

5N

38E

18

13

6/5  
7/8

TSN R38 E

E-5

ORIG SURVEY, 1872 BY GEO. WILLIAMS.

FD: POSSIBLE REMAINS OF THE ORIG NE BEARING TREE, AN ORIG 10" WHITE PINE, NOW A 20" LODGEPOLE PINE STUMP, WITH SCRIBING "BT" PLAINLY VISIBLE ON PREVIOUSLY OPENED FACE, FACING APPROX  $550^{\circ}$  W.

WE ALSO FIND THREE OTHER LODGEPOLE PINE STUMPS IN THE AREA GENERALLY AGREEING IN SIZE WITH THE ORIG NOTES, EACH WITH VISIBLE AXE MARKS AND FACES POINTING TO A COMMON LOCATION, HOWEVER, BEARINGS AND DISTANCE MEASUREMENTS TO THESE POSSIBLE BT'S DO NOT AGREE WITH THE ORIG. NOTES:

IF WE ESTABLISH A POINT AT RECORDED MEASUREMENT TO THE "SCRIBED" STUMP,  $N50^{\circ}E$  (27 LKS) 17<sup>B</sup> FT., WE FIND THE FOLLOWING:

A 24" LODGEPOLE PINE STUMP, WITH VISIBLE AXE MARKS, WE OPEN FURTHER AND FIND NO TRACE OF SCRIBING BEAR:

(OVER)

FILE T Me 6000

← N →

PHOTO  
PHOTO  
FILED  
OBJ  
MAG

FLA  
Sta  
X  
Y  
Date

S 53° E 20<sup>+</sup> FT. (REC S 53° E 42 LKS. OR  
27<sup>2</sup> FT.)

A 20" LODGEPOLE PINE STOB APPROX. 10 FT.  
TALL WITH VISIBLE AXE MARKS AND FACE BEARS  
S 54° W 30° (REC. S 40° E 12 LKS OR 7<sup>2</sup> FT.)

NOTE: BECAUSE OF ITS SIZE, IT APPEARS THAT  
THE ORIGINAL NOTES ARE IN ERROR FOR THIS  
TREE

AND AN 6" LODGEPOLE PINE WINDFALL WITH  
VISIBLE AXE MARKS, BEARS N 42° W 17°  
(REC. N 23° W 20 LKS OR 13<sup>2</sup> FT.)

A SMALL ROCK MOUND AND OLD HAND-HEWN  
POST BEARS S 59° W 7<sup>5</sup> FT.

THE SCRIBING FOUND IS OF THE SAME STYLE  
AND POSITION ABOVE GROUND AS THAT FOUND  
AT THE EAST  $\frac{1}{4}$  SEC 8, ALSO ESTAB. BY  
WILLIAMS. THE OVERGROWTH PORTION PREVIOUSLY  
REMOVED COULD NOT BE FOUND.

23  
5-22-80  
Harry J. Knight ORLS 1099  
GREG. ORTON

COMPASS DECL. 19 $\frac{1}{2}$ ° EAST.