


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. F-9a

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point, set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 24" in ground. No stones available for rock mound.

Bearing Trees:

A White Fir 11" dia. bears N88°W, 79.8 ft., scribed: N 1/16 S8 BT.

A White Fir 15" dia. bears S37°W 58.3 ft., scribed: N 1/16 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on September 24, 1980.

Witnesses: R. Orton
G. Wagoner
L. Huntsman
A. Hanley



Office of..... County Surveyor..... County of..... Umatilla
Oregon..... I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December..... 1980
David Krumbein by *Betty Shatto*
(COUNTY OFFICIAL) (DEPUTY)

R-186-B