

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Index File No. G-9a

History of original corner establishment:

The original surveyor George Williams under G.L.O. Contract No. 176, 1872 set a post from which:

- A White Fir 30" dia. bears S32°W 49 lks.
- A White Fir 15" dia. bears N18°W 72 lks.

In 1899 a resurvey was performed by George R. and William C. Campbell under G.L.O. Contract No. 699. They found the corner and BTs set by Williams in 1872.



Description of corner evidence found:


Found: Original SW bearing tree, and original 30" White Fir, now a 36" broken snag about 10' tall with visible scribing "B" on previously opened blaze. Open further and find scribing "S 1/4 BT". Unable to find post or stone replacing post. No trace of original NW BT.

Description of monument and accessories | established to perpetuate the original location of this corner:

At record bearing and distance from original BT, set a 1"x30" Galvanized Pipe with a 3" brass cap stamped:

Set corner 24" in ground.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



Bearing Trees:

- A Spruce 6" dia. bears N31°W 43.5 ft., scribed: 1/4 S8 BT.
- A Spruce 11" dia. bears S71°W 9.1 ft., scribed: 1/4 S8 BT.

I hereby certify the above corner monument was reestablished as herein described on September 25, 1980.

- Witnesses:
- R. Orton
 - G. Wagoner
 - L. Huntsman
 - A. Hanley



Office of.....County..Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 1980
 Dated.....by.....Betty Shatto.....
 (COUNTY OFFICIAL) (DEPUTY)

R-186-B