


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-9b

History of original corner establishment:

The original surveyor William E. Campbell under G.L.O. Contract No. 699, 1899 set a Spruce post from which:

A Spruce 30" dia. bears N56°E 50 lks. marked 1/4 S9 BT.



Description of corner evidence found:

After a thorough search no evidence of the original BTs or post or stone, set in 1911 by Bradley, could be found.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set at proportioned point a 1"x30" Galvanized Pipe with 3" brass cap stamped:

Set pipe 24" in ground.


Bearing Trees:

A White Fir 19" dia. bears N65°E 45.9 ft., scribed: 1/4 S9 BT.

A Spruce 5" dia. bears S21°E 33.1 ft., scribed: BT on a foot blaze.

Bark scribed 1/4 S9.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on September 25, 1980.

Witnesses: R. Orton  
G. Wagoner  
L. Hunstman  
A. Hanley

Office of.....County.....Surveyor..... County of.....Umatilla.....  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the.....day of.....December.....1980.....  
.....Daniel L. Krumbein by.....Clyde L. Hatt.....  
(COUNTY OFFICIAL) (DEPUTY)