


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-8

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories | established to perpetuate the original location of this corner:

At surveyed point set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Set pipe 24" in ground with mound of stone and dirt to cap.

New BTs:

A White Fir 12" dia. bears N30°E, 78.3 ft., scribed SE 1/16 S8 BT.

A White Fir 14" dia. bears S40°E, 49.1 ft., scribed SE 1/16 S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was established as herein described on October 29, 1980.

Witnesses: R. Orton
A. Hanley

Office of.....County Surveyor..... County of.....Umatilla.....
 Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of December, 1980
, by Betty Shatto
 (COUNTY OFFICIAL) (DEPUTY)