


CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Index File No. J-11

History of original corner establishment: The original surveyor William E. Campbell, under GLO Contract No. 699, set a point 1,000 ft above sec cor and set an ironstone 30x16x6 ins 18" deep in the ground.
Mound of stone firmly about the corner for 1/4 sec corner marked 1/4 on North face, from which:
A Fir 15" dia bears N17°E 42 lks dist marked 1/4 S9 BT.
A Fir 26" dia bears S35°E, 88 lks dist marked 1/4 S16 BT.



Description of corner evidence found: Original stone, firmly set with plain markings "1/4" on North face (markings oriented horizontally), the original stone mound has deteriorated from which:
An original 15" Fir, now a 24" Doug. Fir wind fall, lying approx. 15 ft East (downhill) from its original position, with a well healed blaze visible on the underneath portion of the tree, the root hole of which bears N17°E 27.7 ft. An original 26" Fir, now a 22" Doug. Fir standing and dead, with a well healed blaze bears S28°E 56.4 ft.

Description of monument and accessories I established to perpetuate the original location of this corner: In place of stone set 1"x30" galvanized pipe with 3" brass cap. Buried pipe 20" in ground with original stone buried alongside; brass cap stamped:
Built mound of stone to cap. From which:
A Doug. Fir 13" dia bears S86°E 24.8 ft scribed 1/4 S16 BT.
A Doug. fir 8" dia bears N18°W 59.8 ft. scribed 1/4 S9 BT.
Attached 54-3 & 54-4 signs to both BT's. Attached brass washers stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red.



I hereby certify the above corner monument was re-established as herein described on Oct. 9, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wyatt
A. Hanley

Office of..... County Surveyor..... County of..... Umatilla
Oregon.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December....., 1980
..... David Krumbein..... by..... Betty Slatts.....
(COUNTY OFFICIAL) (DEPUTY)

R-186-B