

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Index File No. J-5a

History of original corner establishment:

In 1872, under G.L.O. Contract No. 176, George Williams set post for Cor. Sec. 7, 8, 17, 18 from which:

- A Spruce 8" dia. bears N12°E 15 lks.
- A White Fir 9" dia. bears N80°W 6 lks.
- A White Fir 12" dia. bears S80°E 26 lks.
- A Spruce 10" dia. bears S35°W 62 lks.

In 1899 a resurvey was done by George R. and William E. Campbell under G.L.O. Contract No. 699. The post set by Williams was destroyed and they set a 15"x10"x6" stone 10" in ground from BTs. Destroyed markings on S.E. & SW BTs.



Description of corner evidence found:

A diligent search was made and no evidence of original stone or BTs could be found. Using calls to streams East, North and South established a point that fit the call distances very well. This evidence is believed to reestablish the corner as near to the original location as possible.

Description of monument and accessories established to perpetuate the original location of this corner:

At established point set 1"x30" Galvanized Pipe with 3" brass cap stamped:


Corner falls in shoulder of dirt road, set pipe 36" deep (6" below surface.)

From which:

A Douglas Fir bears N29½°W 100.1 ft. 8" dia., scribed: T5N R38E S7 BT.

A Spruce 12" dia. bears N74°E 54.4 ft., scribed: T5N R38E S8 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washers stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on November 10, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wagoner

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon..... I hereby certify that the within instrument was filed in this office
for record on the.....day of.....December..... 19..80
.....David L. Lumberman..... by.....Betty Shatt.....
(COUNTY OFFICIAL) (DEPUTY)