


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File: No. J-9a

History of original corner establishment:

In 1872, under G.L.O. Contract No. 176, George Williams set post for corner to 8, 9, 16 & 17 on a steep ridge from which a Red Fir 12" in diameter bears N37°W, 83 lks. dist. A Red Fir 7" in diameter bears S28°W, 84 lks dist.

A resurvey was done by George R. and William E. Campbell in 1899 under G.L.O. Contract No. 699. They found the corner and BT's set by Williams and destroyed marks on S.W. BT.



Description of corner evidence found:

At corner location found unrecorded mound of stones from which a 30" Douglas Fir stump bears N36°W 54.8 ft. Portion of tree is lying near stump with good scribing "S8 B". A 16" D. Fir, alive and in good condition, with open face and no marks visible, bears S18° W. 55.4 ft. (marks were destroyed in 1899).


Description of monument and accessories I established to perpetuate the original location of this corner:

In center of mound of stones set 1"x30" galvanized pipe with 3" brass cap stamped:

Set pipe 25" in ground with mound of stone to cap

Bearing Trees:

- New: A Douglas Fir 20" dia. bears N32°E 96.4 ft. scribed T5N R38E S9 BT.
- A Douglas Fir 19" dia. bears N 7°W, 79.0 ft. scribed T5N R 38E S8 BT
- A Douglas Fir 8" dia. bears S 71° W, 26.9 ft. scribed T5N R38E S17 BT.



Attached 54-3 and 54-4 signs to all BT's. Attached brass washer stamped LS 1294 to foot blaze of new BT's. Painted blazes and 6" band around new BT's Red.

I hereby certify the above corner monument was reestablished as herein described on October 8, 1980.

- Witnesses:
- R. Orton
 - G. Wagoner
 - M. Wyatt
 - A. Hanley



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 19.....80
 ..David B. ... by ..Betty Shatto.....
 (COUNTY OFFICIAL) (DEPUTY)