

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Index File No. J-9b

History of original corner establishment:

The original surveyor, William E. Campbell, under GLO Contract No. 699, 1899, set a point 100 ft. below the N.E. corner of Sec. 17. A rock in place in stone ledge on which he cut a cross (x) at the exact corner point for corner of Sec. 9 & 16, marked with 4 notches on S. and E. edges from which:

A Pine 18" dia. bears N20½°E dist. 199 lks. marked T5N R38E S9 BT.

A Fir 18" dia. bears S88°E 90 lks. dist. marked T5N R38E S16 BT.



Description of corner evidence found:

Rock in place in ledge as described, with faint "+" on top and 4 notches on South and East edges, from which:

The only remaining Bearing Tree, now a 30" Douglas Fir, alive and in good condition, open and find good scribing "S", bears S88°E 66.8 ft.


Description of monument and accessories established to perpetuate the original location of this corner:

At point of "+" drilled hole with star drill and set 2½" brass tablet with 3/4"x3" shaft in hole with mortar stamped:

New BT:

A Douglas Fir 14" dia. bears N70E, 67.5 ft., scribed T5N R38E S9 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of new BT. Painted blazes and 6" band around both BTs red.



I hereby certify the above corner monument was reestablished as herein described on October 21, 1980.

Witnesses: R. Orton
G. Wagoner
M. Wyatt
A. Hanley



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 19.....80
, David R. Hamrick, by Betty Skatto
 (COUNTY OFFICIAL) (DEPUTY)

R-186-R