


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was established by R. Omeg in 1932 under G.L.O. contract no. 761, as a "re-establishment of the Surveys by Rufus Moore, U.S. Deputy Surveyor, in 1882", at which time Mr. Omeg set a 1" iron post 3' long, 27" in ground with brass cap marked "1/4 S. 6 1932", from which a fir 18" diameter bears S 47 E 35 links, and a fir, 12" diameter, bears S 20 W 86 links distant.



Description of corner evidence found:

Found 2 1/2" brass cap on 1" pipe, which protrudes 7" from ground. Also found 30" douglas fir with healed blaze and B.L. M. bearing tree sign S 13 degrees 47 minutes W 58.2 feet from corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

I scribed the new bearing trees " 1/4 BT" at the following relationship to the brass cap and pipe:

30" Douglas fir with curved trunk S 59 degrees 47 minutes West 38.2 feet.

8" White fir S 12 degrees 22 minutes E 8.6 feet

15" Douglas fir S 22 degrees 12 minutes E 14.3 feet

Basis of bearings is based on a solar observation.

REGISTERED PROFESSIONAL LAND SURVEYOR

Paul W. Tomkins

00000000
JULY 26, 1988
PAUL W. P. TOMKINS
2560

Renews 6/30/16
10/14/95

Office of S.W.V.S.P.A.R. County of Umatilla
State of Ore., I hereby certify that the within instrument was filed in this office
for record on the 9 day of October, 1995
David H. K. by Paul W. Tomkins
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor * GPO-708-274
Date 10-95
Rec'd by KK
No. 95-163-R