

Index  
File No.

**CORNER RECORD (SEARCH)**  
(Ref. FSM 5151.4)

Tract or Survey No. **Wenaha-Tucannon Wilderness** Cor. No. **AP 85-26**


T. 5 N. R. 39 E.  
Merid. Willamette

R.D. Pomeroy & Walla Walla County Wallowa  
N.F. Umatilla State Oregon

**CORNER DIAGRAM**

Wenaha-Tucannon  
Wilderness

AP 85-26



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

NONE

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From westerly junction of 6415 and 6415-020 travel easterly on 6415-020 approx. 2.05 miles to steel fence post with Wilderness Boundary sign set on top of the cut bank. From this point follow the Wilderness Boundary S 72 ¼ W, approx. 320 feet to the Angle Point.

**PLANE COORDINATE POSITION DATA**

State: Oregon Zone: North  
X: 2701259.969 meters  
Y: 247467.521 meters  
Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1998

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, stamped "W-T WILDERNESS AP 85-26 RLS 2308 1998".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

16" Western Larch, N 11 E, 58.5 feet, scribed "WB/85-26" "BT".

6" Western Larch, S 57-1/2 E, 33.7 feet, scribed "WB/85-26" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich

Title Land Surveyor

Date 10/1998

State Registration No.  
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At:

Date

REMARKS

Index File No.

T. 5 N.

R. 39 E.

M. Willamette

Tract or Survey No.

Wenaha-Tucannon  
Wilderness

Cor. AP 85-26