

Index  
File No.

## CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

Tract or  
Survey No.Wenaha-Tucannon  
Wilderness

Cor.

No. AP 85-33

T. 5 N. R. 39 E.  
Merid. WillametteR.D. Pomeroy & Walla Walla  
N.F. UmatillaCounty Wallowa  
State Oregon

## CORNER DIAGRAM

Wenaha-Tucannon  
Wilderness  
AP 85-33

## DESCRIBE CORNER MONUMENT FOUND

NONE

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

## PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

## DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From westerly junction of 6415 and 6415-020 travel easterly on 6415-020 approx. 1.50 miles and then walk northerly approx. 200 feet to the Angle Point.

## PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2700834.453 meters

Y: 247746.915 meters

Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1998

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT; DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground stamped "W-T WILDERNESS AP 85-33 RLS 2308 1998".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

22" Western Larch, N 44 E, 44.4 feet, scribed "WB/85-33" "BT".  
13" Subalpine Fir, S 54 1/4 E, 43.3 feet, scribed "WB/85-33" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich Title Land Surveyor Date 10/1998 State Registration No. or Agency \_\_\_\_\_

Certified Corner Record Prepared? Yes  No \_\_\_\_\_ Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index File No.

T. 5 N.

R. 39 E.

M. Willamette

Tract or Survey No.

Wenaha-Tucanon  
Wilderness

Cor. AP 85-33