

## CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

Tract or  
Survey No.Wenaha-Tucannon  
Wilderness

Cor.

No. AP 84-66

T. 5 N.

R. 39 E.

R.D. Pomeroy &amp; Walla Walla

County Wallowa

Merid. Willamette

N.F. Umatilla

State Oregon

## CORNER DIAGRAM

Wenaha-Tucannon  
Wilderness

AP 84-66



## DESCRIBE CORNER MONUMENT FOUND

NONE

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

## PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
From junction of 6415 and 6415-040 (Timothy Springs Guard Station) travel northeasterly on 6415 approx. 1.55 miles and then walk westerly approx. 360 feet to the Angle Point.

## PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2703379.446 meters

Y: 248720.690 meters

Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1998

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, stamped "W-T WILDERNESS AP 84-66 RLS 2308 1997".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

19" Western Larch, S 46 1/2 W, 24.6 feet, scribed "WB/84-66" "BT".

16" Western Larch, N 52 1/4 W, 29.5 feet, scribed "WB/84-66" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich

Title Land Surveyor

Date 10/1998

State Registration No.  
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At

Date

REMARKS

Index File No.

T. 5 N.

R. 39 E.

M. Willamette

Tract or Survey No.

Wenaha-Tucannon  
Wilderness

Cor. AP 84-66