

Index  
File No.

**CORNER RECORD (SEARCH)**

(Ref. FSM 5151.4)

Tract or  
Survey No.

**Wenaha-Tucannon  
Wilderness**

Cor.

No. **AP 85**

**T. 5 N. R. 39 E.**  
**Merid. Willamette**

**R.D. Pomeroy & Walla Walla**  
**N.F. Umatilla**

**County Wallowa**  
**State Oregon**

**CORNER DIAGRAM**

Wenaha-Tucannon  
Wilderness

AP 85



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

NONE

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From junction of 6415 and 6415-040 (Timothy Springs Guard Station) travel northerly 530 feet to the Angle Point located in the center of Trail No. 3106 (Timothy Trail).

**PLANE COORDINATE POSITION DATA**

State: Oregon Zone: North  
X: 2702444.372 meters  
Y: 247661.267 meters  
Datum: NAD83(1991)

Signature

David Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/1998

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground in the center of Trail No. 3106 stamped "W-T WILDERNESS AP-85 RLS 2308 1997".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

14" Lodgepole Pine, N 6 1/2 W, 65.2 feet, scribed "WB\85" "BT".  
26" Western Larch, N 84 3/4 E, 13.3 feet, scribed "WB/85" "BT".  
Steel Fence Post, with Wilderness Boundary sign, S 32 W, 33.1 feet.

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By David Schlaich Title Land Surveyor Date 10/1998 State Registration No. or Agency \_\_\_\_\_  
Certified Corner Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS