


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by George S. Pershin under GLO contract number 430, dated 1882. Surveyor General record states:

Set basalt stone 12x8x8 ins 8 ins in ground for 1/4 sec cor marked 1/4 on W. face; from which,

A Pine 40 ins dia brs N43°E, 111 lks dist. marked 1/4 S BT
No other tree within limits and raised mound of stone alongside.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found stone 12x8x7 inches marked 1/4 S in old rock jack approximately 8 feet East of true corner position.

Found a 40 inch diameter Ponderosa Pine stump N43°E, 111 lks, no scribes visible.

This pine is the only pine of this size in the area and it's relativity to the corner stone confirms that this was indeed the original bearing tree.

Distance to the existing BT is to the face of the blaze.

Description of monument and accessories I established to perpetuate the

original location of this corner: At record bearing and distance from the original bearing tree, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 16 inches in the ground, from which:

New BTs:

A 14 inch diameter Ponderosa Pine bears N34°E, 34.60 feet marked 1/4 S2 BT
A 8 inch diameter Ponderosa Pine bears S80°W, 13.23 feet marked 1/4 S3 BT

Raised a mound of stone around monument, 3 ft. base to top of cap.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.
Set a steel fencepost approximately 5 feet North with land survey monument and property boundary signs attached.
Buried the original corner stone South and alongside of monument.

I hereby certify that the above corner point was perpetuated as hereon described on August 30, 1988.

Witness: Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey County of Umatilla
State of OR, I hereby certify that the within instrument was filed in this office for record on the 22nd day of September, 1988
David H. Kumbier by Kathleen Kumbier
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 9-88
Rec'd By KJ
No. 88-63-P

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276