

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-25

History of original corner establishment: Corner established in 1880 by George S. Pershin under General Land Office Contract No. 373.

Surveyor General Records States:

Set basalt stone 18 x 10 x 8 ins. for cor. to sect's. 6-7-1-12.

- A 6" Pine bears N 26 E, 63 lks.
- A 44" Pine bears S 50 E, 87 lks.
- A 8" Pine bears S 42 W, 59 lks.
- A 10" Pine bears N 23 W, 35 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, 13"x9"x8", properly marked, firmly set in mound of stone in a fence line running North and South, from which:

Original BTs

- A 22" Pine, good condition, bears N29E, 41.6 ft., scribes visible.
- A stump hole bears S50E, 57.4 ft.
- A 22" Pine, good condition, bears S42W, 39.6 ft., scribes visible.
- A 24" Pine, good condition, bears N19W, 24.3 ft., scribes visible.

Description of monument and accessories I established to perpetuate the original location of this corner

At position of stone, I set 2 1/2"x30" iron pipe with brass cap, marked as shown, 24" in ground, from which:

New BT


A 20" Pine bears S77E, 77.2 ft. marked T5S R31E S7 BT.

- Nailed brass washer to BT blaze.
- Buried original stone South and along side pipe.
- Set steel fence post 5+ ft. North of corner.
- Used steel tape and magnetic compass with 20° E declination.
- Measured to face of blaze on original BT and center of new BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane I. Griffith

OREGON
JULY 10, 1974
DUANE I. GRIFFITH
644



Office of Surveyor County of Washtenaw
 State of Michigan, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of August, 1974 at 1 o'clock pm, (signed)
Ralph Thompson by _____
 (COUNTY OFFICIAL) (DEPUTY)

E-25

S-63-M^o