


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-7

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.



Surveyor General Record States:

Set Basalt Stone 14 x 10 x 10 ins. for $\frac{1}{4}$ cor.
Marked $\frac{1}{4}$ on N. face. From which:
A 24" Pine bears N. 72 W. 18 lks.
A 8" Fir bears S. 71 W. 23 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found mound of stone, from which:

A 14" Fir, good condition, bears S72W, 41.8 ft., scribes visible.
A 24" Pine, poor condition, bears N76W, 50.6 ft., scribes visible.

No marked stone was found.

Blazes on these BTs face this mound of stone. It is evident, an error was made in recording the original distances.

Description of monument and accessories established to perpetuate the original location of this corner

In place of mound of stone, I set 2 $\frac{1}{2}$ "x30" iron pipe with brass cap, marked as shown, raised mound of stone, from which:

New BT


A 9" Fir bears N26E, 17.1 ft. marked $\frac{1}{4}$ S5 T5S R30E BT.

Nailed brass washer to BT blaze.

Set steel fence post 5+ ft. West of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BTs and center of new BTs.



Office of *Surveyor* County of *Umatilla*

State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *13* day of *July*, 19*74*, at *11* o'clock *am*, (signed)

Duane J. Griffith by *Philip J. Campbell* (DEPUTY)

E-7