


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.



Surveyor General Record states:

Set basalt stone 15 x 10 x 9 in for corner to Section 9-10-15-16. Marked with 4 notches on South and 3 notches on the East edges, from which:

- A 28" Pine bears N30W, 75 lks.
- A 13" Pine bears N80E, 29 lks.
- A 30" Pine bears S38W, 78 lks.
- A 30" Pine bears S50E, 15 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found stone, call size properly marked in a mound of stone, from which:

Original BTs

- A stump hole bears N80E 19+ ft.
- A 3/4" Pine, good condition, bears S50E, 9.9 ft., scribes visible.
- A 30+'' Pine stump bears S38W, 51.5 ft., BT visible.
- A 32'' Pine, good condition, bears N30W, 49.5 ft., scribes visible.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set 2 1/2" x 30" iron pipe with brass cap marked as shown 25" in ground, from which:


New BTs

- A 15" Fir bears N49E, 27.7 ft. marked T5S R30E S10 BT.
- A 8" Pine bears S72W, 71.6 ft. marked T5S R30E S16 BT.

Nailed brass washer in BT blaze.
 Buried stone South and along side pipe.
 Set steel fence post 5+ ft. East of corner.
 Raised mound of stone 3 ft. at base to top of cap.
 Used steel tape and magnetic compass with 20° E declination.
 Measured to face of blaze on original BTs and center of new BTs.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Duane I. Griffith
 OREGON
 JULY 10, 1966
 DUANE I. GRIFFITH
 644



Office of Surveyor County of Washtenaw
 State of Michigan, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of July, 1974, at 11 o'clock am, (signed)
Ralph J. [Signature] by [Signature] (DEPUTY)

J-13
 I-12/R