

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-21

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set post for cor. to sect's. 11-12-13-14. From which:

- A 30" Pine bears S 38 E, 10 lks.
- A 20" Pine bears N 69 W, 53 lks.
- A 30" Pine bears S 18 W, 83 lks.
- Dug pit 18 x 18 x 12 and raised mound of earth.



No record of subsequent remonumentation was found in County Records. Description of corner evidence found: Found 2 original BTs as follows:

- A 24" Pine, poor condition, bears S37E, 6.6 ft., scribes visible.
- A 30" Pine, good condition, bears S16W, 54.8 ft., scribes visible.

No evidence of other BT or original stake found.

Description of monument and accessories established to perpetuate the original location of this corner

At corner point, based on original BTs, I set 2 1/2"x30" iron pipe with brass cap, marked as shown, 24" in ground, from which:


New BTs

- A 10" Pine bears N28E, 12.2 ft. marked T5S R30E S12 BT.
- A 8" Pine bears S13E, 57.7 ft. marked T5S R30E S13 BT.
- A 18" Pine bears N36W, 77.1 ft. marked T5S R30E S11 BT.

Nailed brass washer to BT blaze. Set steel fence post 5+ ft. North of corner. Used steel tape and magnetic compass with 20° E declination. Measured to face of blaze on original BTs and center of new BTs.

REGISTERED PROFESSIONAL LAND SURVEYOR

DUANE I. GRIFFITH  
JULY 10, 1974  
644



Office of Surveyor County of Wasatch  
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 13 day of Aug, 1974, at ..... o'clock ..... m., (signed) ..... by ..... (COUNTY OFFICIAL) ..... (DEPUTY)

J-21