

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-23

History of original corner establishment: Corner established in 1883 by F. W. Campbell under General Land Office Contract No. 468.

Surveyor General Record States:

Set basalt stone 13 x 8 x 7 ins. for  $\frac{1}{4}$  cor. marked  $\frac{1}{4}$  on N face. From which:

- A 40" Pine bears S 70 W, 139 lks.
- A 10" Pine bears N 60 E, 249 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original stone, call size marked  $\frac{1}{4}$ , 10" in the ground, from which:

Original BT

A 40" Pine snag bears S70W, 89.0 ft., scribes visible.

Found no evidence of other BT.

Description of monument and accessories established to perpetuate the original location of this corner

In position of stone, I set 2 $\frac{1}{2}$ "x30" iron pipe with brass cap marked as shown, 22" in ground, raised mound of stone 6 ft. at base to top of cap, from which:

New BTs

- A 9" Pine bears N38W, 55.4 ft. marked  $\frac{1}{4}$ S12 T5S R30E BT.
- A 10" Pine bears S68W, 33.1 ft. marked  $\frac{1}{4}$ S13 T5S R30E BT.

Nailed brass washer to BT blazes.

Corner of fences running South and West bears N30E, 6.0 ft.

Buried original stone North and along side pipe.

Set steel fence posts 5+ ft. South and 5+ ft. West of corner.


Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BT and center of new BTs.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Handwritten signature*

OREGON  
JULY 10, 1924  
DUANE I. GRIFFITH  
644



Office of *Surveyor* County of *Umatilla*  
 State of *Oregon*, I hereby certify that the within instrument was filed in this office  
 for record on the *13* day of *Aug*, 19*74*, at *11* o'clock *am*, (signed)  
*Ralph Thompson* (COUNTY OFFICIAL) *[Signature]* (DEPUTY)

J-23