


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner originally established by Frank W. Campbell under GLO contract number 468, dated 1883. Surveyor General record states: Set basalt stone 15x15x4 ins 10 ins in ground for ¼ sec cor marked ¼ on W face; from which:
 A pine 20 ins dia brs N70°W 70 lks. dist. marked ¼S BT
 A pine 10 ins dia brs S40°E 15 lks. dist. marked ¼S BT
 Corner remonumented by BLM in 1978. BLM notes state: The ¼ sec cor of secs 25 and 32, monumented with the original unmarked basalt stone, 15x15x4 ins, loosely set in a mound of stone from which the remains of the original bearing trees:
 A pine 26 ins diam bears S40°E 15 lks dist with healed blaze.
 A root hole bears N65°W 70 lks dist with a down pine alongside 22 ins dist with scribes visible on open blaze. (Record, N70°W).
 At the corner point:
 Set an iron post 28 ins long 2½ ins diam 15 ins in the ground and in a mound of stone 3 ft. base to top with brass cap marked (shown below) from which a new bearing tree:
 A fir 19 ins diam bears N37½°W, 120 lks dist mkd ¼ S26 BT. Deposit corner stone alongside iron post.
 No record of subsequent monumentation found in Umatilla County survey records.



Description of corner evidence found:

Found a 2½" standard BLM brass cap monument marked as shown in mound of stone.

Found original and BLM bearing trees as described in the BLM record above. Distances to existing BTs are to the center of the tree



Description of monument and accessories established to perpetuate the original location of this corner:

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 8, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



Office of Surveyor County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office for record on the 28th day of June, 1989.
David H. Kramdorn by Kathleen S. Amshuey
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 6-89
 Rec'd by LA
 No. 89-62-R

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

T-21