


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-21

History of original corner establishment:

Frank W. Campbell under G.L.O. contract no. 468, dated Apr. 12, 1883, set a basalt stone 15"x 15"x 4" marked "1" on the west face and marked BTs:
A Pine, 20" dia., N70°W, 70 lks.
A Pine, 10" dia., S40°E, 15 lks.

Craig L. Wanless, Cadastral Surveyor, under Special Instructions, Group No. 350, dated Mar. 27, 1978, found the original stone of record size and:
A Pine, 26" dia., S40°E, 15 lks.; with a healed blaze.
A root hole, N65°W, 70 lks.; down Pine alongside with scribing visible.
At the corner point he set a 2 1/2"x 28" iron post with a brass cap marked:
He marked a new BT:
A Fir, 19" dia., N37 1/2°W, 120 lks.



T5S R30E
1/4
S26 S25

T5S R30E
1/4
S26 S25
1978

Description of corner evidence found:

I found a 2 1/2" iron pipe with a 3 1/4" brass cap (BLM) marked as above. The monument is surrounded by a mound of stone.
From the corner:

A Douglas Fir, 21" dia., N37 1/2°W, 79.2 ft.; with a healed blaze.
A Ponderosa Pine, 20" dia., S40°E, 9.9 ft.; with a healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

I marked new BTs:

A Ponderosa Pine, 12" dia., N72°E, 45.4 ft.; mkd.: X at breast height and BT at base.
A Douglas Fir, 9" dia., S63 1/4°W, 31.6 ft.; mkd.: X at breast height and BT at base.

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BTs have, additionally, alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E.

May 16, 1990



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL)

(DEPUTY)
RECEIVED BY

Umatilla County Surveyor
Date 1-91
Rec'd By KA
No. 91-010-A