


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Refer to: Plat of L-P Coop. Survey for the U.S. Forest Service  
Section 26, T.5S., R.30E., W.M. U-21

History of original corner establishment:  
No record of previous monumentation.



Description of corner evidence found:  
None..

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point, established by measurement, I set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap mkd.:  
Monument is 16" in ground and surrounded by a mound of stone.

S1/16  
S26|S25  
PLS 1832  
1990

From the corner:

- A Ponderosa Pine, 13" dia., S37°E, 20.4 ft.;  
mkd.: S1/16 S25 BT.
- A Ponderosa Pine, 12" dia., S33 1/4°W, 40.4 ft.;  
mkd.: S1/16 S26 BT.

BTs have blaze and a 6" band painted red, BT tags, "Land Survey Monument" signs and alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E..

May 16, 1990



Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor, PO-790-276  
Date 1-91  
Rec'd By KA  
No. 91-010-A