


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1880
by George S. Pershin, under Contract No. 361

Surveyor General Record States:

80.00 set basalt stone 16x8x7 on S.W. slope for cor. to
sec. 31 and 32:

Pine 20 in. in diam. brs. N. 73° W. 34 lks. dist.
Pine 22 in. in diam. brs. N. 38° E. 22 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found basalt stone 16"x8"x7" marked with 5 notches on E. edge and 1 notch on W. edge,
firmly set in a mound of stone. From which the ORIGINAL BEARING TREES:

A 22" pine bears N. 69° W. 22.4 ft. mkd. T5S S31 SC BT in weathered blaze.
A stump hole bears N. 38° E. 14.5 ft., no remains of this BT found.

Description of monument and accessories | established to perpetuate the
original location of this corner:

At the corner point: Set a 2½"x30" iron pipe 20" in the ground with brass cap
marked as shown. From which I scribe NEW BEARING TREES:

A 10" pine bears N. 71° E. 49.2 ft. mkd. T5S R30E S32 SC BT.
An 8" pine bears N. 22° W. 10.5 ft. mkd. T5S R30E S31 SC BT.


I nailed a brass washer mkd "OPLS 598" to the BT blaze of both trees. Set a steel
fence post 5 ft. East of corner. Buried original corner stone W and alongside pipe.
Raised mound of stone 3 ft. base to within 3" of top of pipe. Corner is 22 ft. N.
of E-SW fence line. Used compass with 20° East variation and steel tape, measuring
to center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept 30, 1976



Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

2-5