


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1880 by George S. Pershin, under Contract No. 361.

Surveyor General Record States:

80.00 set basalt stone 20x10x8 on East slope for cor. to sec. 32 and 33:

A fir 15 in. in diam. brs. N. 52° W. 70 lks. dist.  
A pine 12 in. in diam. brs. N. 17° E. 62 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

Found basalt stone 20"x9"x7" marked with 4 notches on one edge and 2 notches on opposite edge. This stone was loosely set in dim mound of stone. From which the ORIGINAL BEARING TREES:

A 24" fir bears N. 52° W. 46.2 ft. marked 30 E. S32 SC in partially opened blaze.  
A stump hole of a deteriorated pine bears N. 17° E. 40.9 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point: Set a 2½"x30" galvanized iron pipe 24" in the ground with brass cap marked as shown. From which I scribe one NEW BEARING TREE:

A 20" fir bears N. 34° E. 33.0 ft. mkd. T5S., R. 30E S33 SC BT.


I nailed a brass washer marked "OPLS 598" in the BT blaze of this tree. Set a steel fence post 5 ft. East of corner in fenceline. Buried original corner stone East and alongside iron pipe. Raised a mound of stone to within 2" of top of pipe. Corner is 1 ft. South of E-W fenceline. Used compass with 20° East variation and steel tape, measuring to center of BT.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Robert D. Bagett*

OREGON  
JULY 12, 1903  
ROBERT D. BAGETT  
598

*Sept. 30, 1976*



Office of..... County Surveyor..... County of..... Umatilla.....  
State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)