

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Z - 7
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on October 3, 1880, under GLO contract No. 373, as follows:

Set basalt stone 18" x 14" x 10" in a mound of stones on a northeast slope for 1/4 section corner, from which:

A 10" pine bears N38°E, 64 links (42.24 feet).



Corner evidence recovered:

Found a small mound of stones at the corner point. The corner area has been disturbed by logging slash burning, and the corner stone is gone. The original 10" pine bearing tree is now a 19" Ponderosa Pine with scribes "1/4S" visible on a previously opened upper blaze. The lower blaze is healed.

Monument and accessories established to perpetuate the original location of this corner:

At record bearing and distance from the original bearing tree (S38°W, 42.24 feet), I set a 1" x 30" iron pipe 13" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 12" into the ground surrounded by a mound of stones with a 3/4" brass washer, marked "PLS 1636 SE", attached to the rod, bears S11°E, 124.7 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S46°W, 84.5 feet.

A 24" Ponderosa Pine scribed "1/4 S32 BT" on double blazes bears N0°30'W, 69.4 feet. This tree has a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B". Both bearing trees have a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on July 13, 1998. Magnetic declination: 18°E.

REGISTERED PROFESSIONAL LAND SURVEYOR
Dennis L. Gaylord
OREGON JULY 14, 1978 DENNIS L. GAYLORD 1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 9-98
Rec'd By RR
No. 98-186R