


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Q-2

Index No. Q-2

History of original corner establishment:

None



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 29 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence posts South and West of corner on property line and attached signs 54-2 and 54-9.

Established 2 new BT's: A 11" red fir bears N86°E 116.2 ft. scribed SW 1/16 S 19BT.

A 7 1/2 " Tamarack bears N35°W 41.9 ft. scribed SW 1/16 S 19BT.

New BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

New BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Location poster on west side of road 25'+ East of corner .

NOTE: This corner was established in error in 7/79 and bearing trees established. When the corner was established in its true position, scribing and signs were removed from one BT referencing the erroneous position. From the correct corner position: A 9 1/2" red fir bears S89°E 87.8 ft. with open blaze. Used steel tape and magnetic compass with 19 1/2° east declination. Measured to center of Bts.

See map of survey

This corner set August 12, 1979

Witnesses: Greg Flower L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

T55 R31E  
SW 1/16 S19  
1979  
PLS 1106

Office of County Surveyor County of Umatilla  
State of Oregon , I hereby certify that the within instrument was filed in this office  
for record on the        day of        .  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B